

GSP PROMETEU



GSP PROMETEU

DRILLING RIGS •

Future Upgrade

www.gspoffshore.com



GRUP SERVICII PETROLIERE

member of UPETROM GROUP



TECHNICAL DATA

GENERAL

Rig Type:	Four legs, self elevating unit
Design:	Sonnat Offshore Company
Builder:	Galatzi Shipyard, Romania
Year Built:	1984, rebuilt in 2003
Classification:	ABS
Flag:	Malta
Accommodation:	96 + 2 Hospital
Helideck:	80 x 80 ft, rated for PUMA SA 330 B
Max. Drill Depth:	20,000 ft
Max. Water Depth:	300 ft (91 m)
Operating Conditions:	Wave: 30 ft @ 12 sec; Wind: 50 knots; Surface Current: 2 knots
Storm Conditions:	Wave: 39 ft @ 10 sec; Wind: 100 knots; Surface Current: 2 knots

TECHNICAL DIMENSIONS

Length:	172 ft / 52.42 m
Breadth:	162 ft / 49.38 m
Depth:	21 ft / 6.40 m
Ocean Transit Draft:	32 ft / 9.75 m
VDL – Operating:	2,205 st / 2,000 mt

CAPACITIES

Liquid Mud:	1,880 bbls / 10,560 cuft / 299 m ³
Drill Water:	3,482 bbls / 19,535 cuft / 553 m ³

Potable Water:	1,272 bbls / 7,135 cuft / 202 m ³
Fuel Oil:	1,595 bbls / 9,172 cuft / 253 m ³
Bulk Mud:	4,620 cuft / 131 m ³
Bulk Cement:	4,620 cuft / 131 m ³
Sack Material:	1,000 sacks

DRILLING EQUIPMENT

Derrick:	Upetrom, 164 ft x 34.7 ft x 30 ft; 1,000 kips dynamic load
Drawworks:	NOV, ADS 10 D, 3,000 HP
Driller's Cabin:	Dual Chairs, NOV Amphion System
Top Drive:	NOV, TDS 8 SA – 750 tons
Rotary:	Upetrom, MRL-375, 37 ½ in opening, independent drive
Pipe Handling:	PRS-8i Cat Walk P10 -45 LS Automated Fingers Board Iron Roughneck AR 3200 NOV Power Slips PS -21 NOV BX 4-75 Hydraulic Elevator NOV HC-26 EV Dual Cathead NOV Fox Hole Spider
Mud Pumps:	3 x triplex PN 2,000 HP x 7,500 PSI
Shale Shakers:	4 x Mongoose Swaco, PT Dual Motions
Desilter & Desander:	1 x Swaco, 16 x 4 in cones, 1,000 gpm
Mud Cleaner:	Mongoose PT Dual Motions
BOP:	1 x 13 - 5 / 8 in T3 Energy Service 10 K annular, 1 x 13 - 5 / 8 in T3 15 K single, 1 x 13 - 5 / 8 in T3 15 K double



TECHNICAL DATA



Diverter:	MSP 29 ½ in x 500 psi with 2 x 12 in tri-centric valves
Control System:	Koomey UET 302460-A85461-32-11 SB, 3,000 psi
Choke & Kill:	1 x 3 in x 15 K choke manifold with 2 x 3 - 1 / 16 in x 15 K remote control chokes 1 x 3 - 1 / 16 in x 15 K manual choke
Cementing:	Schlumberger Cementing Unit (Third Party)

MACHINERY

Main Power:	5 x Caterpillar 3512 Engines, 8,430 HP total, 600 V, AC
Emergency Power:	1 x Caterpillar C -18 DITA Engine, 587 HP, 400 V, AC
Power Distribution:	9 x Siemens SIMOREG, DC Master 6 RA 7093-4 KS 22-0-2, 600 V
Deck Cranes:	2 x AmClyde 10,000 HD, 40 mt @ 6 m, 1 x AmClyde 10,000 LD, 25 mt @7.5 m

JACK-UP SPECIFICATIONS

Legs:	Triangle; 4 x 400 ft; usable bellow hull = 347 ft
Leg Spacing:	Longitudinal 126 ft; Transverse 109 ft
Spud Cans:	4 x 38.83 ft diameter x 8.11 ft height
Jacking System:	Orion Class Pin & Hole
Cantilever / Slot:	Cantilever type 55 ft x 20 ft

MOORING EQUIPMENT

Winches:	2 ea x 20 to, B type, electric drive
Wire / Chain:	1 ¼ in x 300 m
Anchors:	2 x 4.5 to Hall





GRUP SERVICII PETROLIERE

member of UPETROM GROUP

Constanta Port, Berth 34, 900900,
Constanta, Romania • office@gspoffshore.com
Tel.: +40 24 155 5255 • Fax: +40 24 155 5257

www.gspoffshore.com